

|                                          |                                                     |                                        |
|------------------------------------------|-----------------------------------------------------|----------------------------------------|
| PROJECT                                  | PREPARED FOR                                        | DOCUMENT                               |
| Harbor Point Medical Office — Building B | Brightline Builders, Inc.                           | Revision1                              |
| PRJ - 2026-0412                          | 1550 Wewatta St, Denver, CO 80202                   | Proposal / bid ref. Q-2026-0412        |
| 2200 Harbor Point Blvd, Denver, CO 80216 | Attn: Marcus Reed, Project Manager · (303) 555-0192 | Agreement ref. Subcontract SC-2026-118 |
|                                          |                                                     | Prepared by Dana Whitfield             |

PROJECT OVERVIEW — building, size, phase, and the drawings, specifications and addenda this scope is based on

Mechanical and plumbing scope for Building B, a two-story, 28,400 SF medical office building. This scope of work is Exhibit A to Subcontract SC-2026-118 and is based on the drawings and the Division 22 and 23 specifications dated April 6, 2026, including addenda 1 and 2.

INCLUDED WORK one row per area or system — mirror the schedule of values so scope and billing line up

| # | AREA / SYSTEM                      | DESCRIPTION OF WORK INCLUDED                                                                                         | QTY / SPEC REF         |
|---|------------------------------------|----------------------------------------------------------------------------------------------------------------------|------------------------|
|   | General                            | Mobilization, submittals, coordination drawings, mechanical and plumbing permits                                     | 1 LS · 01 30 00        |
|   | Underground                        | Sanitary and storm below slab: 4"–8" PVC, cleanouts, trench and backfill within the building footprint               | P-101 · 22 13 13       |
|   | Domestic water                     | Type L copper mains and branches, valves, backflow preventer; install owner-furnished water heater WH-1              | P-201–P-203 · 22 11 16 |
|   | Sanitary waste & vent              | No-hub cast iron above grade, vents through roof, floor drains and trap primers                                      | P-301 · 22 13 16       |
|   | HVAC equipment                     | RTU-1 to RTU-4 on curbs, split-system air handlers AHU-1 to AHU-3 with condensing units; crane set by Summit         | M-501 · 23 74 13       |
|   | Ductwork & distribution            | Galvanized supply, return and exhaust ductwork; 18 VAV terminals with reheat; diffusers and grilles per schedule     | M-201–M-204 · 23 31 13 |
|   | Refrigerant & hydronic piping      | Refrigerant piping to split systems, condensate drains, hydronic piping to reheat coils                              | M-401–M-402 · 23 21 13 |
|   | Controls & BMS                     | DDC controllers, sensors and actuators; integration to the owner's existing BMS front end for the points in 23 09 00 | M-601 · 23 09 00       |
|   | Insulation                         | Duct wrap and liner, pipe insulation per schedule                                                                    | 23 07 13 · 23 07 19    |
|   | Plumbing fixtures & trim           | 48 fixtures per P-601 schedule with carriers, stops and trim                                                         | P-601 · 22 40 00       |
|   | Testing, balancing & commissioning | Pressure tests, TAB by certified agency, functional testing and commissioning support                                | 23 05 93 · 01 91 13    |
|   | Closeout                           | Record drawings, O&M manuals, warranties, 4 hours of owner training                                                  | 01 78 00               |

EXCLUSIONS — work, materials and fees not included — one item per line; anything not excluded here is included

Electrical power wiring, disconnects and starters to mechanical equipment  
Fire sprinkler and fire alarm systems, including duct detector wiring  
Furnishing of water heater WH-1 (owner-furnished; installation is included)  
Roofing, flashing and structural framing at roof penetrations and RTU curbs  
Concrete housekeeping pads; slab cutting and patching outside the mechanical scope  
Medical gas piping and outlets  
Painting of exposed ductwork and piping  
Permit fees other than mechanical and plumbing permits  
Overtime or shift work not shown in the milestone schedule  
Hazardous-material testing and abatement

ASSUMPTIONS AND CLARIFICATIONS — site access, working hours, sequencing, lead times, and the documents the price is based on

Site available and underground work released by June 8, 2026; slab pour on or about June 29.  
Normal working hours Monday–Friday, 7:00 a.m.–3:30 p.m.; one mobilization per phase.  
Summit provides the crane and rigging for a one-day RTU set; Brightline coordinates roof access and the street closure.  
BMS integration is limited to the points listed in 23 09 00; front-end software licenses are by the owner.  
RTU lead time is 10–12 weeks from approved submittal; the schedule assumes approval by June 22.  
Pricing is based on the drawings dated April 6, 2026 and addenda 1 and 2.

WORK BY OTHERS

what this scope depends on, who provides it, and when

| ITEM FURNISHED OR PERFORMED BY OTHERS                          | BY WHOM                  | NEEDED BY                    |
|----------------------------------------------------------------|--------------------------|------------------------------|
| Power wiring, disconnects and starters to mechanical equipment | Electrical subcontractor | Before start-up (Aug 24)     |
| Roof curb flashing and roofing patch at RTU curbs              | Roofing subcontractor    | Before RTU set (Aug 17)      |
| Structural steel supports at RTU-2 curb per S-201              | General contractor       | Before RTU set (Aug 17)      |
| Water heater WH-1 — furnish only; Summit installs              | Owner                    | Delivered by Jul 15          |
| Concrete housekeeping pads                                     | General contractor       | Jul 20                       |
| Fire alarm duct detector wiring and interlocks                 | Fire alarm subcontractor | Before commissioning (Nov 2) |

MATERIALS AND SUBMITTALS

basis of design and when the submittal is due

| MATERIAL / EQUIPMENT                                         | BASIS OF DESIGN / SPEC SECTION | SUBMITTAL DUE |
|--------------------------------------------------------------|--------------------------------|---------------|
| Packaged rooftop units RTU-1 to RTU-4, 12.5–25 ton, gas heat | Basis of design per 23 74 13   | Jun 8, 2026   |
| Ductwork shop drawings and VAV terminal schedule             | 23 31 13 · 23 36 00            | Jun 15, 2026  |
| Plumbing fixtures and trim                                   | P-601 schedule · 22 40 00      | Jun 8, 2026   |
| DDC controls: points list, sequences, panel drawings         | 23 09 00                       | Jun 22, 2026  |
| Duct and pipe insulation                                     | 23 07 13 · 23 07 19            | Jun 8, 2026   |

SCHEDULE MILESTONES

| MILESTONE                                 | START        | FINISH       |
|-------------------------------------------|--------------|--------------|
| Mobilization, submittals and coordination | Jun 1, 2026  | Jun 19, 2026 |
| Underground sanitary and storm            | Jun 8, 2026  | Jun 26, 2026 |
| Domestic water and DWV rough-in           | Jul 6, 2026  | Aug 14, 2026 |
| Rooftop unit set (crane)                  | Aug 17, 2026 | Aug 19, 2026 |
| Ductwork, refrigerant and hydronic piping | Aug 3, 2026  | Sep 25, 2026 |
| Controls and insulation                   | Sep 14, 2026 | Oct 16, 2026 |
| Fixtures and trim                         | Oct 12, 2026 | Oct 30, 2026 |
| Testing, balancing and commissioning      | Nov 2, 2026  | Nov 13, 2026 |
| Closeout, O&M manuals and training        | Nov 16, 2026 | Nov 18, 2026 |

ACCEPTANCE CRITERIA — the tests, inspections, documents and sign-offs that mean the Work is complete

The Work is complete when all systems have been pressure-tested and the TAB report shows airflows within ±10% of design; controls are verified point-to-point and trended for 48 hours; plumbing tests are witnessed by the inspector and Brightline; the mechanical and plumbing finals are signed off; record drawings, O&M manuals and warranties are delivered; and owner training is complete.

ATTACHMENTS

☒ Drawings   ☒ Specifications   ☒ Proposal / bid   ☒ Schedule of values   ☐ Unit prices   ☐ Site photos

Prepared and accepted

This scope of work, with its attachments, defines the Work under the agreement referenced above. Items not listed as included, and not reasonably inferable from the referenced documents, are excluded. Changes to this scope are made only by written change order.

Prepared by · Summit Mechanical Contractors

Accepted by · Brightline Builders, Inc.

SIGNATURE

SIGNATURE

Dana Whitfield, Project Manager

05/11/2026

Marcus Reed, Project Manager

05/18/2026

PRINTED NAME AND TITLE

DATE

PRINTED NAME AND TITLE

DATE

General-purpose form, not legal advice. Attach this scope of work to the agreement as an exhibit so it controls; where it conflicts with the drawings or specifications, the order of precedence in the agreement decides. Keep the revision number and date current whenever the scope is renegotiated.