

Summit Mechanical Contractors

4120 Industrial Way, Suite 200, Denver, CO 80216
(303) 555-0148 · office@summitmech.com · Lic. C-2214-MC

Estimate

EST-2026-041 · April 30, 2026

PROJECT	PREPARED FOR (GC / OWNER)	ESTIMATE
Harbor Point Medical Office — Building B	Brightline Builders, Inc.	Date
PRJ-2026-0412	1550 Wewatta St, Denver, CO 80202	Pricing valid through
2200 Harbor Point Blvd, Denver, CO 80216	Attn: Marcus Reed, Project Manager · (303) 555-0192	Bid due
BID DOCUMENTS & ADDENDA — drawing set, spec divisions, addenda acknowledged	PREPARED BY	REVIEWED BY
M-001–M-602 & P-001–P-402 dated 03/27/2026 · Div. 22 & 23 · Addenda 1–2	Priya Natarajan, Estimator	Dana Whitfield, Project Manager

#	DESCRIPTION	QTY	UNIT	UNIT COST	AMOUNT
MATERIALS					delivered cost, before sales tax
1	Packaged rooftop units RTU-1 to RTU-4 with curbs, economizers & BACnet controllers Budget quote — Front Range Equipment Sales, per M-601 schedule	1	LS	\$74,800.00	\$74,800.00
2	Air devices, VAV terminals & fire/smoke dampers per M-401 / M-402	1	LS	\$16,250.00	\$16,250.00
3	Type L copper pipe, fittings & valves — domestic water	2,860	LF	\$11.40	\$32,604.00
4	Cast iron & PVC DWV pipe, fittings & hangers	3,120	LF	\$8.75	\$27,300.00
5	Plumbing fixtures & trim per P-601 schedule	42	EA	\$385.00	\$16,170.00
6	Refrigerant & hydronic piping, controls hardware & specialties	1	LS	\$20,276.00	\$20,276.00
Materials subtotal					\$187,400.00
LABOR					qty = hours · unit cost = fully loaded hourly rate
7	Plumbers — underground, rough-in & trim	780	HR	\$68.50	\$53,430.00
8	Pipefitters — refrigerant, hydronic & equipment set	300	HR	\$71.00	\$21,300.00
9	Sheet metal — air devices, dampers & RTU set	180	HR	\$66.00	\$11,880.00
10	Foreman — supervision, layout & coordination	240	HR	\$84.00	\$20,160.00
Labor subtotal					\$106,770.00
EQUIPMENT					rentals, crane, tools
11	Crane — 90-ton hydraulic for RTU sets, incl. rigging crew	2	DAY	\$3,850.00	\$7,700.00
12	Scissor & boom lifts (4 mo), press tools & core drill rental	1	LS	\$7,000.00	\$7,000.00
Equipment subtotal					\$14,700.00
SUBCONTRACTORS					written quotes attached
13	Sheet metal ductwork — fabricate & install Ridgeline Sheet Metal quote dated 04/28/2026	1	LS	\$31,850.00	\$31,850.00
14	Pipe & duct insulation — Front Range Insulators	1	LS	\$9,487.00	\$9,487.00
15	Testing, adjusting & balancing — Rocky Mountain TAB (independent)	1	LS	\$5,600.00	\$5,600.00
16	Controls programming & BMS integration — Alpine Controls	1	LS	\$5,795.00	\$5,795.00
Subcontractors subtotal					\$52,732.00

BASIS OF ESTIMATE, ASSUMPTIONS & EXCLUSIONS — what the price relies on — carry these onto the proposal

Pricing per bid set dated 03/27/2026 and Addenda 1–2. Excludes medical gas, fire protection, power wiring to equipment (Div. 26), roof flashing, structural dunnage, cutting/patching and utility fees. Installation of owner-furnished water heater WH-1 carried at \$1,980. Bonds not included (add 1.2% if required). Sales tax at Denver 8.81% on materials. Bid submitted as a \$486,200 lump sum on proposal BP-2026-041.

Direct cost subtotal	\$361,602.00
Sales tax on materials (8.81%)	\$16,509.94
Contingency (3% of direct cost)	\$10,848.06
Total estimated cost	\$388,960.00
Overhead (10%)	\$38,896.00
Cost + overhead	\$427,856.00
Profit — 12% margin on price	\$58,344.00

Margin, not markup. Overhead is a cost, priced before profit. Profit is a share of the price: price = (cost + overhead) ÷ (1 – margin). A 12% margin here equals a 13.6% markup on cost + overhead.

Estimate total \$486,200.00

Internal pricing worksheet — the customer-facing number and the assumptions above go on your quote or bid proposal. Not accounting or tax advice: confirm the sales-tax treatment of materials for your state and contract.