

Summit Mechanical Contractors

4120 Industrial Way, Suite 200, Denver, CO 80216
(303) 555-0148 · office@summitmech.com · Lic. C-2214-MC

Schedule of values

Revision 2 · September 3, 2026

PROJECT		SUBMITTED TO (OWNER / GENERAL CONTRACTOR)		CONTRACT	
Harbor Point Medical Office — Building B		Brightline Builders, Inc.		Contract date	May 18, 2026
PRJ - 2026-0412		1550 Wewatta St, Denver, CO 80202		Original contract sum	\$486,200.00
2200 Harbor Point Blvd, Denver, CO 80216		Attn: Marcus Reed, Project Manager · (303) 555-0192		Net approved change orders	\$5,370.00
				Contract sum to date	\$491,570.00
DATE		REVISION / REASON — e.g. "Initial SOV with application no. 1" or "adds CO-004"			
September 3, 2026		Adds CO-001 and CO-002 as lines; submitted with application no. 3			

ITEM NO.	DESCRIPTION OF WORK	SCHEDULED VALUE	% OF CONTRACT	NOTES / BASIS
1	Mobilization & submittals	\$14,600.00	2.97%	Submittals, bonds, temporary facilities
2	Underground sanitary & storm	\$38,400.00	7.81%	
3	Domestic water rough-in	\$52,800.00	10.74%	
4	Sanitary waste & vent rough-in	\$61,200.00	12.45%	
5	HVAC equipment (RTU-1 to RTU-4)	\$96,500.00	19.63%	Equipment 72% · rigging & set 28%
6	Ductwork & distribution	\$88,700.00	18.04%	By area: L1 40% · L2 35% · roof 25%
7	Refrigerant & hydronic piping	\$41,300.00	8.40%	
8	Controls & BMS integration	\$33,600.00	6.84%	
9	Insulation	\$18,900.00	3.84%	
10	Plumbing fixtures & trim	\$24,700.00	5.02%	
11	Testing, balancing & commissioning	\$9,800.00	1.99%	Billed on acceptance of the TAB report
12	Closeout, O&M manuals & training	\$5,700.00	1.16%	O&M manuals, training, as-builts
APPROVED CHANGE ORDERS — ADDED AS LINES WHEN APPROVED				
CO-001	Relocate RTU-2 curb per structural revision S-201 Rev. 1	\$7,350.00	1.50%	Approved July 8, 2026
CO-002	Delete owner-furnished water heater; credit installation only	-\$1,980.00	-0.40%	Approved July 29, 2026
	Original schedule of values	\$486,200.00	98.91%	
	Net approved change orders	\$5,370.00	1.09%	
Total scheduled value — must equal the contract sum to date		\$491,570.00	100.00%	
Every line is a percentage of the contract sum to date; the percentages add to 100.00%. If the total and the contract sum differ, a line is missing or a change order was never added.				

Submitted and accepted

The scheduled values above are the basis for progress billing on this contract until a revised schedule is accepted.

Prepared by (contractor) · Summit Mechanical Contractors

Accepted by (owner / GC) · Brightline Builders, Inc.

	Dana Whitfield, Project Manager	09/03/2026		Marcus Reed, Project Manager	09/05/2026
SIGNATURE	PRINTED NAME AND TITLE	DATE	SIGNATURE	PRINTED NAME AND TITLE	DATE

Match the line items to how the work actually phases and keep every value defensible on a walkthrough. Add approved change orders as new lines with the CO number as the item number, so the schedule always ties to the contract sum your pay applications bill against. Not an AIA document.