

PROJECT	PREPARED FOR	DOCUMENT
Harbor Point Medical Office — Building B	Brightline Builders, Inc.	Revision 1
PRJ - 2026-0412	1550 Wewatta St, Denver, CO 80202	Proposal / bid ref. Q-2026-0412
2200 Harbor Point Blvd, Denver, CO 80216	Attn: Marcus Reed, Project Manager · (303) 555-0192	Agreement ref. Subcontract SC-2026-118
		Prepared by Dana Whitfield

PROJECT OVERVIEW — building, size, phase, and the drawings, specifications and addenda this scope is based on

Mechanical and plumbing scope for Building B, a two-story, 28,400 SF medical office building. This scope of work is Exhibit A to Subcontract SC-2026-118 and is based on the drawings and the Division 22 and 23 specifications dated April 6, 2026, including addenda 1 and 2.

INCLUDED WORK one row per area or system — mirror the schedule of values so scope and billing line up

#	AREA / SYSTEM	DESCRIPTION OF WORK INCLUDED	QTY / SPEC REF
	General	Mobilization, submittals, coordination drawings, mechanical and plumbing permits	1 LS · 01 30 00
	Underground	Sanitary and storm below slab: 4"–8" PVC, cleanouts, trench and backfill within the building footprint	P-101 · 22 13 13
	Domestic water	Type L copper mains and branches, valves, backflow preventer; install owner-furnished water heater WH-1	P-201–P-203 · 22 11 16
	Sanitary waste & vent	No-hub cast iron above grade, vents through roof, floor drains and trap primers	P-301 · 22 13 16
	HVAC equipment	RTU-1 to RTU-4 on curbs, split-system air handlers AHU-1 to AHU-3 with condensing units; crane set by Summit	M-501 · 23 74 13
	Ductwork & distribution	Galvanized supply, return and exhaust ductwork; 18 VAV terminals with reheat; diffusers and grilles per schedule	M-201–M-204 · 23 31 13
	Refrigerant & hydronic piping	Refrigerant piping to split systems, condensate drains, hydronic piping to reheat coils	M-401–M-402 · 23 21 13
	Controls & BMS	DDC controllers, sensors and actuators; integration to the owner's existing BMS front end for the points in 23 09 00	M-601 · 23 09 00
	Insulation	Duct wrap and liner, pipe insulation per schedule	23 07 13 · 23 07 19
	Plumbing fixtures & trim	48 fixtures per P-601 schedule with carriers, stops and trim	P-601 · 22 40 00
	Testing, balancing & commissioning	Pressure tests, TAB by certified agency, functional testing and commissioning support	23 05 93 · 01 91 13
	Closeout	Record drawings, O&M manuals, warranties, 4 hours of owner training	01 78 00

EXCLUSIONS — work, materials and fees not included — one item per line; anything not excluded here is included

Electrical power wiring, disconnects and starters to mechanical equipment
Fire sprinkler and fire alarm systems, including duct detector wiring
Furnishing of water heater WH-1 (owner-furnished; installation is included)
Roofing, flashing and structural framing at roof penetrations and RTU curbs
Concrete housekeeping pads; slab cutting and patching outside the mechanical scope
Medical gas piping and outlets
Painting of exposed ductwork and piping
Permit fees other than mechanical and plumbing permits
Overtime or shift work not shown in the milestone schedule
Hazardous-material testing and abatement

ASSUMPTIONS AND CLARIFICATIONS — site access, working hours, sequencing, lead times, and the documents the price is based on

Site available and underground work released by June 8, 2026; slab pour on or about June 29.
Normal working hours Monday–Friday, 7:00 a.m.–3:30 p.m.; one mobilization per phase.
Summit provides the crane and rigging for a one-day RTU set; Brightline coordinates roof access and the street closure.
BMS integration is limited to the points listed in 23 09 00; front-end software licenses are by the owner.
RTU lead time is 10–12 weeks from approved submittal; the schedule assumes approval by June 22.
Pricing is based on the drawings dated April 6, 2026 and addenda 1 and 2.

WORK BY OTHERS

what this scope depends on, who provides it, and when

ITEM FURNISHED OR PERFORMED BY OTHERS	BY WHOM	NEEDED BY
Power wiring, disconnects and starters to mechanical equipment	Electrical subcontractor	Before start-up (Aug 24)
Roof curb flashing and roofing patch at RTU curbs	Roofing subcontractor	Before RTU set (Aug 17)
Structural steel supports at RTU-2 curb per S-201	General contractor	Before RTU set (Aug 17)
Water heater WH-1 — furnish only; Summit installs	Owner	Delivered by Jul 15
Concrete housekeeping pads	General contractor	Jul 20
Fire alarm duct detector wiring and interlocks	Fire alarm subcontractor	Before commissioning (Nov 2)

MATERIALS AND SUBMITTALS

basis of design and when the submittal is due

MATERIAL / EQUIPMENT	BASIS OF DESIGN / SPEC SECTION	SUBMITTAL DUE
Packaged rooftop units RTU-1 to RTU-4, 12.5–25 ton, gas heat	Basis of design per 23 74 13	Jun 8, 2026
Ductwork shop drawings and VAV terminal schedule	23 31 13 · 23 36 00	Jun 15, 2026
Plumbing fixtures and trim	P-601 schedule · 22 40 00	Jun 8, 2026
DDC controls: points list, sequences, panel drawings	23 09 00	Jun 22, 2026
Duct and pipe insulation	23 07 13 · 23 07 19	Jun 8, 2026

SCHEDULE MILESTONES

MILESTONE	START	FINISH
Mobilization, submittals and coordination	Jun 1, 2026	Jun 19, 2026
Underground sanitary and storm	Jun 8, 2026	Jun 26, 2026
Domestic water and DWV rough-in	Jul 6, 2026	Aug 14, 2026
Rooftop unit set (crane)	Aug 17, 2026	Aug 19, 2026
Ductwork, refrigerant and hydronic piping	Aug 3, 2026	Sep 25, 2026
Controls and insulation	Sep 14, 2026	Oct 16, 2026
Fixtures and trim	Oct 12, 2026	Oct 30, 2026
Testing, balancing and commissioning	Nov 2, 2026	Nov 13, 2026
Closeout, O&M manuals and training	Nov 16, 2026	Nov 18, 2026

ACCEPTANCE CRITERIA — the tests, inspections, documents and sign-offs that mean the Work is complete

The Work is complete when all systems have been pressure-tested and the TAB report shows airflows within ±10% of design; controls are verified point-to-point and trended for 48 hours; plumbing tests are witnessed by the inspector and Brightline; the mechanical and plumbing finals are signed off; record drawings, O&M manuals and warranties are delivered; and owner training is complete.

ATTACHMENTS

☒ Drawings ☒ Specifications ☒ Proposal / bid ☒ Schedule of values ☐ Unit prices ☐ Site photos

Prepared and accepted

This scope of work, with its attachments, defines the Work under the agreement referenced above. Items not listed as included, and not reasonably inferable from the referenced documents, are excluded. Changes to this scope are made only by written change order.

Prepared by · Summit Mechanical Contractors

Accepted by · Brightline Builders, Inc.

SIGNATURE

SIGNATURE

Dana Whitfield, Project Manager

05/11/2026

Marcus Reed, Project Manager

05/18/2026

PRINTED NAME AND TITLE

DATE

PRINTED NAME AND TITLE

DATE

General-purpose form, not legal advice. Attach this scope of work to the agreement as an exhibit so it controls; where it conflicts with the drawings or specifications, the order of precedence in the agreement decides. Keep the revision number and date current whenever the scope is renegotiated.